MYSORE DIVISION.

The 25th November 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore division, up to 20th December 1897, for restoring and improving the Homma tank, Registered No. 36 of Chamrajnagar taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1899.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Mysore between the hours of 11 A. M. to 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and be accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring and improving the Homma tank, Registered No. 36 of Chamrajnagar taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items.	*Per.*	*Quantity.*	*Rate.*
Bund—			
Earthwork	C. yd.	45,003	
Turfing	Sqr.	27,881	
Rough stone revetment	C. yd.	1,340	
Fixing new grade stones with lead and edge stones	No.	72	
Gauge stone	„	1	
Register number stone	„	1	
B. M. stones	„	2	
Clearing jungle	Lump sum.		
Waste weir—			
Extending weir	R. ft.	200	
Sluices—			
Examining and repairing / New sluices	Lump sum.		
Distribution—			
Constructing an acqueduct	„		
Supply—			
Improving feeder channel	„		

C. A. MAHADEVA SASTRI, *Executive Engineer.*

HASSAN DIVISION.

The 6th December 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan division, up to 10th January 1898, for restoring and extending the Changravalli anikat and channel. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1899.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Hassan between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring and extending the Changravalli anikat and channel;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Western Circle, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the